The earnest money to be deposited along with the tender is Rs. 380.
The last date for receiving tenders is 26th February 1938, before 3 P.M.

M. A. RAMANUJAM,
Assistant Engineer.

HASSAN DIVISION.

Abstract Notification dated the 6th February 1938.

The attention of the public is invited to the Notification published in *Mysore Gazette* dated 10th February 1938, *vide* pages 202-204, Part VI, calling for tenders for "Constructing first floor to the Administrative Block of Sri Chamarajendra Hospital at Hassan". The last date for receipt of tenders is 26th February 1938.

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Notification dated 19th February 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, up to 3 P.M. on 14th March 1938, for constructing a Bridge across Herur Halla at 2/1 of Herur-Basarikatte Road.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Kadur Division, Chikmagalur, should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, and should be superscribed as "Tender for constructing a Bridge across Herur Halla at 2/1 of Herur-Basarikatte Road." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender should be accompanied by a deposit of Rs. 335 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. Cash amount will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date at the time of opening. The final acceptance of the tender will rest with the Executive Engineer, Kadur, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Kadur Division, Chikmagalur, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Kadur Division, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities in estimate are only approximate and are liable to alteration, omissions, deductions or additions, at the discretion of the Executive Engineer, Kadur Division, or his representative. The tendered rates will hold good for any quantity whether it is higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and be handed over to the Public Works Department by the end of December 1938, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 100 which will be recovered from the contractor's outstandings for the period exceeded by him over the time specified above.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer, Kadur Division, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Kadur Division, Chikmagalur.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will be, however, considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

Abstract estimate for constructing a bridge across Herur Halla at 2—1 of Herur-Basarikatte Road.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Clearing site of Bridge and forming valley and benching rock, if necessary	L. S.	..	..	
2	Earthwork excavation of foundation in hard soil including stony gravel	C.yds.	..	245	
3	Burnt stone jelly in surki, cement combination concrete for foundation 1 : 6	C.ft.	..	868	
3(*a*)	Do do with quartz jelly ..	..	..	..	
4	Burnt size stone in cement composite surki mortar 1 : 8 complete with bond stones every 6 feet apart	C.ft.	..	2,649	
5	New burnt stone slabs 6″ thick nicely dressed and fixed	S.ft.	..	184	
6	Pointing with cement mortar 1 : 3 to exposed masonry portions after proper raking joints	Sqr.	..	12.22	
7	Providing and fixing R. S. beams complete of Tatas tested quality	Cwt.	..	66.5	
8	R.C.C. deck slabs (1 : 2 : 4) complete cast on the R.S. beams and finished with cambre, etc. as per design including centring charges ..	C.ft.	..	493	
9	R.C. ornament pillasters as per design complete finished	No.	..	12	
10	C.I. hand railing 1½″ pipes in T. iron uprights ..	R.ft.	..	100	
11	Providing expansion joints to R.C.C. decking ..	,,	..	68	
12	Bailing out water during construction ..	L.S.	..	..	
13	Earthwork to embankment to form approach roads from 1 & 2/1 and to 2 & 3/1 to bridge	C.yds.	..	1,131	
14	Collecting, spreading and consolidating 1½″ soling quartz jelly metal including lead ..	,,	..	63	
(*a*)	Do do 1½″ metal for surfacing with lead	,,	..	32	
(*b*)	Do do gravel with lead ..	,,	..	21	

C. R. IYENGAR,
Executive Engineer.